


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Q-5

History of original corner establishment:

None

Index No. Q-5



No record of subsequent remonumentation found in County Records .
Description of corner evidence found:

None

Description of monument and accessories established to perpetuate the original location of this corner

At the corner position a 2 inch by 30 inch iron pipe, with brass cap marked as shown, was set 5 inches in the ground and surrounded with a mound of stones to the cap .

Set steel fence posts North and East of corner on property line and attached signs 54-2 and 54-9. Established two (2) new BT's:

A 13 1/2" bull pine bears N80°E 75.6 ft. scribed S 1/16 S20 BT.

A 8 1/2" bull pine bears S70 1/2°W 29.2 ft. to center, scribed S 1/16 S 19 BT.

BT's have lower blaze scribed BT with a brass washer stamped PLS 1106 nailed to it.

BT's have 54-3 and 54-4 signs attached and a 6" red band painted around them above blaze.

Location poster on South side of road 850' North of corner.

Used steel tape and magnetic compass with 19 1/2° east declination . Measured to center of Bts.


See map of survey

This corner set August 13, 1979

Witnesses: Greg Flowers L.S.I.T.
Brent Reynolds

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells
OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106



Office of County Surveyor County of Umatilla
State of Oregon , I hereby certify that the within Instrument was filed in this office
for record on the day of
..... by
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Surveyor

Date Sept 4 1979

Rec'd By M. Hughes

No. Q-1164-B