


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

1-7

History of original corner establishment:

None

Index No. T-4



No record of subsequent remonumentation found in County Records .  
Description of corner evidence found:

None

Description of monument and accessories established to perpetuate the original location of this corner

At the corner position a 2 inch by 30 inch iron pipe, with brass cap marked as shown, was set 20 inches in the ground and surrounded with a mound of stones to the cap .

Set steel fence post North and West of corner and attached signs 54-2 and 54-9.

Established 2 new BT's: A 13" bull pine bears S75°E 114.5 ft. scribed CE 1/16 S 30 BT.

A 13 1/2" bull pine bears S52 1/2°E 91.3 ft. scribed CE 1/16 S 30 BT.

BT's have a lower blaze scribed BT with a brass washer stamped PLS 1106 nailed to it.

BT's have 54-3 and 54-4 signs attached and a 6" red band painted around them above blaze.

Location poster on West side of road 300' east of corner.


Used steel tape and magnetic compass with 19 1/2° east declination . Measured to center of Bts.  
See map of survey

This corner set August 20, 1979

Witnesses: Greg Flowers L.S.I.T.  
Brent Reynolds

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

William R. Wells  
OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106



Office of County Surveyor County of Umatilla  
State of Oregon, I hereby certify that the within instrument was filed in this office  
for record on the day of  
by  
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Surveyor

Date Sept 4, 1979

Rec'd By M. Hughes

No. Q-1164-B