

Index  
File No. Z-19


**CORNER RECORD (SEARCH)**

(Ref. FSM 7151.4)

Tract or Survey No. \_\_\_\_\_ Cor. No. \_\_\_\_\_

T 5S R. 32E R.D. Ukiah County Umatilla  
Merid. Willamette N.F. Umatilla State Oregon

**CORNER DIAGRAM**



**DESCRIBE CORNER MONUMENT FOUND** U.S. Dept. of Interior  
Found an iron pipe, firmly set, Bureau of Land Management  
2 1/2 ins. diam., 8" above ground, S C  
in a mound of stone, 3 ft. base, T 5 S R 32 E  
to top, with brass cap mkd, 1/4 S 35  
1968

**DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND**  
A larch, 10 ins. diam., bears N. 2° E., 12 lks. dist., with  
scribe marks 1/4 S BT visible on opened blaze. (Original BT)  
A fir, 10 ins. diam., bears N. 55° W., 51 lks. dist., with  
well-healed single blaze.

**PHOTO IDENTIFICATION DATA**

Photo No. 280-232  
Filed At. UMATILLA NAT. FOR.  
Object Ident. DIRECT  
Ident. By S. J. Langley  
*S. J. Langley*

**DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER**

Corner located 10 ft. south of an E-W fence.

**PLANE COORDINATE POSITION DATA**

State \_\_\_\_\_ Zone \_\_\_\_\_  
X \_\_\_\_\_  
Y \_\_\_\_\_  
Estab. By \_\_\_\_\_ Agency \_\_\_\_\_

*S. J. Langley*  
Signature

Title LS 1099 Division \_\_\_\_\_ Headquarters \_\_\_\_\_ Date 9-17-84 7100-52-(3, 68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

None

ACCESSORIES DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

None

Work Done By Gary Langlitz Title Land Surveyor Date 8-84 State Registration No. 1099  
or Agency

Certified Cor. Record Prepared? Yes  No Filed At \_\_\_\_\_ Date \_\_\_\_\_

REMARKS

Index File No. Z-19 T. 55 R. 32E M. Willamette Tract or Surv. No. \_\_\_\_\_ Cor. \_\_\_\_\_