


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

The corner was originally established by George S. Pershin under Contract No. 390 dated May 12, 1881. The original notes state that a 5" square wood post was set in a mound of stones for corner. No bearing trees were available.



No record of subsequent remonumentation found in County Records .
Description of corner evidence found:

None. Corner was re-established by double proportion measure.

Description of monument and accessories established to perpetuate the original location of this corner

At the corner position a 2 inch by 30 inch iron pipe, with brass cap marked as shown, was set 10 inches in the ground and surrounded with a mound of stones. Set steel fence post north and east of corner and attached 54-2 to both posts & 54-4 to one post. No BT's available. Set 4 reference monuments. Reference monuments are 2"x30" galvanized iron pipes with brass caps set 10" in ground with a mound of stones around them. Set fence post and attached sign 54-4 near each reference monument.

From the corner:

- | | | | |
|--|----------------------------------|----------------------------------|---------------------------------|
| (1) A R.M. bears N77° W 29.89 ft marked: | ① T4S R32E
S36
RM
29.89 | ② T4S R33E
S31
RM
21.81 | ③ T5S R33E
S6
RM
14.94 |
| (2) A R.M. bears N17½° E 21.81 ft. marked: | | | ④ T5S R32E
S1
RM
35.59 |
| (3) A R.M. bears S39° E 14.94 ft. marked: | 1979
PLS1106 | 1979
PLS1106 | 1979
PLS1106 |
| (4) A R.M. bears S64° W 35.59 ft. marked: | | | 1979
PLS1106 |

Used steel tape and magnetic compass with 19½° east declination. Measured to center of R.M.'s
See map of survey


This corner set July 26, 1979

Witnesses: Greg Flowers, L.S.I.T.
Brent Reynolds

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106



Office of County Surveyor County of Umatilla
State of Oregon I hereby certify that the within instrument was filed in this office
for record on the day of

..... by
(COUNTY OFFICIAL) (DEPUTY)

2-25

RECEIVED BY
Umatilla County Surveyor
Date August 20, 1979
Rec'd By M. Blighes
No. Q-1134-B corresponding drawing