


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

None



2-14

Description of corner evidence found:

None


Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2½" Dia. Brass Cap on a 2½" x 30" dia. galvanized pipe set 22" in ground marked as shown:

From which:

A 6" dia. Pine Bears S 44°W, 82.0 feet scribed T 5S. R 33E 1/16 S 3 BT.

A 8" dia. Pine Bears N 88°30'E, 135.6 feet scribed T 4S, R 33E 1/16 S 34 BT.



Blazes are painted red, trees have a red band painted around them. Trees have sign numbers 54-3, 54-9, and brass washers stamped PLS 933 nailed to them.

Bearings were run with a staff compass set at a declination of 19°30'E, distances were measured with a steel tape to the center of the tree.

June 16, 1983

By: Rod Punches
Witness: Brent Reynolds



Office of..... County Surveyor..... County of..... Umatilla
State of..... Oregon....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)



☆ GPO-798-276

84-171 R