


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

B-13

History of original corner establishment:

This corner was monumented by Duane Griffith, PLS 644, during a survey in Section 3 in 1975. He set a 2½"x30" iron pipe with a brass cap marked:

T5S R33E
N 1/16
S3 | S2
1975
PLS 644



From which:

A Lodgepole, 5" dia., N85°W, 5.8 ft.
A Lodgepole, 8" dia., S52°E, 10.7 ft.

Description of corner evidence found:

Found a 2½" iron pipe with a brass cap marked according to the record.

From which:

A Lodgepole 6" dia., N84½°W, 5.7 ft, with scribing visible.
A Lodgepole stump, 6" dia., S52°E, 10.6 ft. with scribing visible.

Description of monument and accessories established to perpetuate the original location of this corner:

Marked a new BT:

A Lodgepole, 6" dia., N61½°E, 46.0 ft. marked: N1/16 S2 BT

BTs have blaze and a 6" stripe painted red, a BT tag and a "Land Survey Monument" sign. The new BT has, additionally, an alum. "PLS 1832" washer nailed to the bottom of the blaze. There is a 6' steel fence post with a "Land Survey Monument" sign within 5' of the corner.

Measured to center of BTs using steel tape and staff compass. Magnetic declination set at 18°E.

September 15, 1984.



Office of... Surveyor County of... Umatilla
State of... Oregon I hereby certify that the within instrument was filed in this office
for record on the 10 day of October 1984
by David H. Keumbein (DEPUTY)
(COUNTY OFFICIAL)