Index File No	B-25				(Ref. FSM 7	(SEARCH)		lo	Cor. N 1/16
T	R	33E	_ R.D	<u>Ukiah</u>		County	<u>Umatilla</u>		
Merid	<u>Willam</u>	<u>ette</u>	<u> N.F. </u>	<u>Umatil</u>	<u>la</u>	. State	Oregon		
CORNER DIA	AGRAM		DESCR	IBE CORNE	MONUME	NT FOUND			
N 1/ N33E	4	R33½E	No	corner	was orig	inally s	et.		
N S1		S 3	DESCR	RE REARING	TREES OR	OTHER OFF	ICIAL ACCESSO	100 00	
1	,				INCES OR	OTHER OFF	ICIAL ACCESSO	RIES FOUND	
I			Nor	ne set.					
			ł						
			6						
PHOTO IDEN	TIFICATION	N DATA							
Photo No	_	_	ł						
Filed At									
Object Iden	it	ц	DESCRI	BE CORNER	LOCATION	PELATIVE TO	NEAD BY CCAT	11050 4100 1101	V TO REACH CORNER
Ident. By									
		nature .	- Cor	ner fall	s in ro	cky outcr	opping at	North end o	of draw
PLANE COOR	DINATE POS	SITION DATA	app	rox. 120	0 feet i	North of	State High	way No. 244	or araw
State	Zone .		.1				a sa sa mi gi	nay 110. 244	•
x									
Y									
Y Estob. By	Age	ney							

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT T5S N 1/16 At surveyed point set 3" brass tablet in mortar in large rock out-**R33E** cropping stamped. **S1** 1980 OR PLS 1294

ACCESSORIES DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

Bearing Trees: A Ponderosa Pine 5" dia. bears S770W, 106.2 ft., scribed N 1/16 S1 BT.

A Juniper 9" dia. bears $N51^{0}W$, 29.7 ft., scribed N 1/16 S1 BT.

Attached 54-3 and 54-4 signs to both BTs. Attached brass washer stamped LS 1294 to

foot blaze of both BTs. Painted blazes and 6" band around both BTs. red. Attached 54-2 and 54-4 sign to metal post 6 ft. south of corner. Attached 54-2 and 54-9 signs to metal post 12 ft. west of corner.

Work Done By. R. C. Orton	Time Party Chief	Date 6/23/80 State Registration No.	
Certified Cor. Record Prepared ? Yes	No Filed At:	Date	
-	REMARKS		
Witnesses: R. Orton			

G. Orton

D. Allen

M.

Tract or Surv. No.

Cor.

R33⅓E

S3

Index File No. R. B-25 33E