

USDA-FOREST SERVICE

Index
File No. D-23

T 5S R. 33E

Merid. Willamette

CORNER RECORD (SEARCH)


(Ref. FSM 7151.4)

R.D. Ukiah County Umatilla

N.F. Umatilla State Oregon

Tract or
Survey No. _____ Cor. No. CS 1/16

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

No corner was originally set.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None set.

PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At. _____

Object Ident. _____

Ident. By _____

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

Signature

Howard R. Damp

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner falls on old E-W fence approx. 12 ft. East of East edge of paved road to Lehman Springs. Road No. 5160.

Title

Division
ORLS

Headquarters
1294

Date
9/77

7100-52-(3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

At surveyed point set 2½"x30" galvanized pipe
with brass cap stamped:
Set pipe 24" in ground with mound of stone to cap

T5S R33E
C
S 1/16 | S1
C
1980
OR PLS 1294

9

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

Bearing Trees:

A Tamarack 5" dia., bears S64⁰E, 31.3 ft., scribed CS 1/16 S1 BT.
A Tamarack 7" dia., bears N60⁰E, 16.4 ft., scribed CS 1/16 S1 BT.

Attached 54-3 and 54-4 signs to both BTs. Attached brass washer stamped LS 1294 to foot blaze of both BTs. Painted blazes and 6" band around both BTs Red. Attached 54-2 and 54-4 signs to metal post 6 ft. East of corner. Attached 54-2 and 54-9 signs to wood post 12 ft. South of corner

10

Work Done By R. C. Orton Title Party Chief Date 6/18/80 State Registration No. or Agency _____

Certified Cor. Record Prepared? Yes No Filed At: _____ Date _____

11

REMARKS

Witnesses: R. Orton
G. Orton
D. Allen

Index File No.	T.	R.	M.	Tract or Surv. No.	Cor.	13
D-23	5S	33E	Willamette		U.S. G.P.O. 1977-725-576/586	13