

USDA-FOREST SERVICE

Index  
File No. D-25

T 5 S R. 33 E

Merid. Willamette

**CORNER RECORD (SEARCH)**


(Ref. FSM 7151.4)

R.D. Ukiah County Umatilla

N.F. Umatilla State Oregon

Tract or Survey No. \_\_\_\_\_  
Cor. No. S 1/16

**CORNER DIAGRAM**



**DESCRIBE CORNER MONUMENT FOUND**

No corner was originally set.

**DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND**

None set.

**PHOTO IDENTIFICATION DATA**

Photo No. \_\_\_\_\_  
Filed At. \_\_\_\_\_  
Object Ident. \_\_\_\_\_  
Ident. By \_\_\_\_\_  
*Signature*

**PLANE COORDINATE POSITION DATA**

State \_\_\_\_\_ Zone \_\_\_\_\_  
X \_\_\_\_\_  
Y \_\_\_\_\_  
Estab. By \_\_\_\_\_

**DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER**

Corner falls 31 ft. East of North and West fence corner. Locate Southeast corner S1 on USFS Rd. No. 5160-290 and walk North 1300 ft. to corner.

*Signature*  
*Howard G. [unclear]*

Title \_\_\_\_\_ Division ORLES Headquarters 1294 Date 9/77  
7100-52-(3/68)

**CORNER RECORD (PERPETUATION)**

**MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT**

At surveyed point set 2½"x30" galvanized pipe with brass cap stamped:

Set pipe 22" in ground with mound of stone to cap.

1 T5S  
S 1/16 R33½E  
R33E  
S1 S3  
1980  
OR PLS 1294

**ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE**

Bearing Trees:

A Lodgepole Pine, 7" dia., bears N15°W, 33.5 ft., scribed S 1/16 S1 BT.

A Lodgepole Pine, 9" dia., bears S61°W, 71.1 ft., scribed S 1/16 S1 BT.

Attached 54-3 and 54-4 signs to both BTs. Attached brass washer stamped LS 1294 to foot blaze of both BTs. Painted blazes and 6" band around both BTs red. Attached 54-4 & 54-2 signs to metal post 5 ft. North of corner. Attached 54-2 and 54-9 signs to metal post 5 ft. West of corner.

10

Work Done By R. C. Orton Title Party Chief Date 6/18/80 State Registration No. or Agency \_\_\_\_\_

Certified Cor. Record Prepared ? Yes No Filed At: \_\_\_\_\_ Date \_\_\_\_\_ 11

**REMARKS**

Witnesses: R. Orton  
G. Orton  
D. Allen

12

Index File No.	T.	R.	M.	Tract or Surv. No.	Cor.	13
D-25	5S	33	Willamette		U.S. G.P.O. 1977-725-576/586	