


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established in 1882 by George S. Pershin under General Land Office Contract No. 430. Surveyor General Records state:
 Set Basalt stone 15 X 10 X 5 ins. for cor. to sec.s 3, 4, 9, 10 from which:
 A Pine 10 ins. dia. brs. S 14° E, 121 lks. dist.
 A Pine 18 ins. dia. brs. S 66° W, 105 lks. dist.
 No other trees near, raised mound of stone along side.



Nor record of subsequent remonumentation was found in county records.


Description of corner evidence found:

Found stone 15" X 10" X 5" marked, loose on the ground.
 Found SE BT loose on ground 75+ ft. Southerly of corner.
 Found SW BT dead and down in place.

(See map of Survey, dated December, 1975)

Description of monument and accessories established to perpetuate the original location of this corner

At record bearing and distance from SW BT I set 2 1/2" X 30" iron pipe with brass cap marked as shown 20" in ground, from which:
 A. 12" Pine bears N 80° E, 17.4 ft. marked T5S R33E S3 BT.
 A 6" Fir bears S 30° E, 54.8 ft. marked T5S R33E S10 BT.
 A 8" Fir bears S 33° W, 50.3 ft. marked T5S R33E S9 BT.
 A 8" Pine bears N 42° W, 54.2 ft. marked T5S R33E S4 BT.
 Buried stone East and along side pipe.
 Raised mound of stone 5 ft. base to top of cap.
 Set steel fence post 5+ft. East.



REGISTERED
PROFESSIONAL
LAND SURVEYOR

Duane I. Griffith
 OREGON
 JULY 10, 1934
 DUANE I. GRIFFITH
 644

Brass Washer nailed to BT blazes.
 Used steel tape and magnetic compass with 19° 30' East declination.
 Measured to center of all BTs.

Office of..... County of.....
 State of....., I hereby certify that the within instrument was filed in this office for record on the day of.....
 by
 (COUNTY OFFICIAL) (DEPUTY)

E-13