


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

5-7

History of original corner establishment:

Corner was originally established by George S. Pershin under Contract No. 430 dated March 23, 1882. The original notes state that at the corner a 16" x 10" x 8" marked basalt stone was set 11" in the ground on a slight N.E. slope from which:
 A 16" pine bears N36°W 26LKS (17.2 ft) marked 1/4 S BT
 A 12" pine bears N40°E 67 LKS (44.2 ft.) marked 1/4 S BT



No record of subsequent remonumentation found in County Records .

Description of corner evidence found:

Found a stone 16" x 10" x 8" buried about 6". No evidence of marks.
 A 20" down and dead pine bears N38°W ± 17.2 ft. scribed 1/4 S BT

Description of monument and accessories established to perpetuate the original location of this corner

At the corner position a 2 inch by 30 inch iron pipe, with brass cap marked as shown, was set 12 inches in the ground and surrounded with a mound of stones to the cap .

Set steel fence post on section line S of corner and attached sign 54-4.

Buried stone by monument on North side,

Established 2 new BT's:

A 10 1/2" red fir bears N81°W 83.5 ft. scribed 1/4 S8BT

A 21" red fir bears S37°E 84.6 ft. scribed 1/4 S 9 BT

New BT's have a lower blaze scribed BT with brass washer stamped PLS 1106 nailed flush.

Attached signs 54 3 & 54-4 and painted red ring around all BT's

Used steel tape and magnetic compass with 19 1/2° east declination . Measured to center of Bts.

See map of survey


This corner set 7-2-79

Witnesses: Greg Flowers L.S.I.T.
 Brent Reynolds

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

William R. Wells

OREGON
 JULY 22, 1977
 WILLIAM R. WELLS
 1106



Office of.....County Surveyor..... County of.....Umatilla.....
 State of.....Oregon....., I hereby certify that the within instrument was filed in this office
 for record on the day of.....
 by
 (COUNTY OFFICIAL) (DEPUTY)

G-9

RECEIVED BY

Umatilla County Surveyor

Date August 20, 1979

Rec'd By M. Bligher

No. Q-1134-B corresponding drawing