


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. H-23


History of original corner establishment:

No corner was originally set.



Description of corner evidence found:

Description of monument and accessories established to perpetuate the original location of this corner: At surveyed point set 2 1/2"X30" galvanized pipe with brass cap stamped: Set pipe 22" in ground with mound of stone to cap.



Bearing Trees:

A Douglas Fir 11" dia bears N81°W, 8.8 ft., scribed CS1/16 S12 BT.  
 A White Fir 8" dia bears N72°E, 18.8 ft., scribed CS1/16 S12 BT.

Attached 54-3 & 54-4 signs to both BTs. Attached brass washer stamped LS1294 to foot blaze of both BTs. Painted blazes and 6" band around both BTs Red. Attached 54-2 & 54-4 signs to metal post 5 ft north of corner. Attached 54-2 & 54-9 signs to metal post 5 ft east of corner.

I hereby certify the above corner monument was established as herein described on 7-8-80.

Witnesses: R. Orton  
 L. Huntsman  
 D. Allen



Office of..... County Surveyor..... County of..... Umatilla  
 State of..... Oregon....., I hereby certify that the within instrument was filed in this office for record on the..... day of..... December....., 19.....80  
 David Hunsman..... by..... Betty Shatto.....  
 (COUNTY OFFICIAL)..... (DEPUTY)