USDA-FOREST SERVICE		· ,		
Index File No. H-23 T 5S R 33 E	_ (RECORD (SEARCH) Ref. FSM 7151.4)	Tract or Survey No	Cor. CS 16
' ——— "· —— <u>-</u>	_ R.D. <u> Ukiah</u> _	County	Jmatilla 💮 💮	
Merid. <u>Willamette</u>	_ N.F. <u>Umatill</u>		re gon	
CORNER DIAGRAM	DESCRIBE CORNER	MONUMENT FOUND		
$S = \frac{1}{16} \oint_{C} S12$	None Sēt			
1	DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND			
		THE ON OTHER OFFICE	INT MODESSORIES FOUND	
•	None Set			
PHOTO IDENTIFICATION DATA	6			
	.			
Photo No	-			
Object Ident	-			
Ident. By	- DESCRIBE CORNER	LOCATION RELATIVE TO 1	EAR-BY FEATURES, ALSO	HOW TO REACH CORNER
Signature	- I			
PLANE COORDINATE POSITION DATA	Location tag	on Road.	f dirt road USFA	No. 5160-410.
State Zone	.	,		
x				
Υ				
Estab. By		•		
Howard Ly	Title	Division Headqu ORLS 129		7100-52·(3/68)
		711-7 14:	<u>9</u> - 77	5_

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT T5S R33E At surveyed point set 2 1/2"X30" galvanized pipe with brass cap stamped: Set pipe 22" in ground with mound of stone to cap. 1980 OR PIG 1201 ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE Bearing Trees: A Douglas Fir 11" dia bears N81°W, 8.8 ft., scribed CS1/16 S12 BT. A White Fir 8" dia bears N72°E, 18.8 ft., scribed CS1/16 S12 BT. Attached 54-3 & 54-4 signs to both BTs. Attached brass washer stamped LS 1294 to foot blaze of both BTs. Painted blazes and 6" band around both BTs Red. Attached 54-2 & 54-4 signs to metal post 5 ft north of corner. Attached 54-2 & 54-9 signs to metal post 5 ft east of corner. Work Done By R. C. Orton Title Party Chief Date 7-8-80 State Registration No. Date Certified Cor. Record Prepared ? (Yes) N٥ Filed At: REMARKS R. Orton Witnesses: L. Huntsman D. Allen

Index File No. T. R. M. Tract or Surv. No. Cor.
U.S. G.P.O. 1977-725-576/5