

USDA-FOREST SERVICE

Index
File No. B-17

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or
Survey No. _____

Cor.
No. N 1/16

T 5S R. 33 1/2E

R.D. Ukiah

County

Umatilla


Merid. Willamette

N.F. Umatilla

State

Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

None Set

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None Set

PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At. _____

Object Ident. _____

Ident. By _____

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner falls on steep rocky south slope approximately 200 ft north of State Hwy No. 244.

Signature

Howard & Co

Title

Division
ORLS

Headquarters
1294

Date
9-77

7100-52-(3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

At surveyed point set 2 1/2" X 30" galvanized pipe with
brass cap stamped:
Set pipe 10" in ground to rock with mound of stone to cap

T5S R33 1/2E
N 1/16
S3 + S2
1980
OR PLS 1294

9

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

Bearing Trees:

A Ponderosa Pine 7" dia. bears S70W, 100.2 ft., scribed N1/16S3 BT.
A Ponderosa Pine 7" dia. bears N 720E, 72.7 ft., scribed N1/16 S2 BT.

Attached 54-3 & 54-4 signs to both BT's. Attached brass washer stamped LS 1294 to foot blaze of both BTs. Painted blazes and 6" band around both BT's red. Attached 54-2, 54-4 & 54-9 signs to metal post 6 ft west of corner.

10

Work Done By R. C. Orton Title Party Chief Date 7-9-80 State Registration No. or Agency _____

Certified Cor. Record Prepared? (Yes) No Filed At: _____ Date _____

11

REMARKS

Witnesses: R. Orton
L. Huntsman
D. Allen

12

Index File No. B-17 T. 55 R. 33 1/2 E M. _____ Tract or Surv. No. _____ U.S. G.P.O. Cor. 1977-725-576/586

13