


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. C-18

History of original corner establishment:

No corner was originally set.




Description of corner evidence found:

Description of monument and accessories I established to perpetuate the original location of this corner: At surveyed point set 2 1/2"x30" galvanized pipe with brass cap stamped:
Set pipe 16" in ground to rock with mound of stone to cap.

Bearing Trees:

A P. Pine 23" dia. bears N66°E, 32.8 ft., scribed CW 1/16 S2 BT.
A P. Pine 8" dia. bears N7°W, 83.4 ft., scribed CW 1/16 S2 BT.
Attached 54-3 and 54-4 signs to both BTs. Attached brass washer stamped LS 1294 to foot blaze of both BTs. Painted blazes and 6" band around both BTs red. Attached 54-2, 54-4 and 54-9 signs to metal post 5' south of corner.



I hereby certify the above corner monument was established as herein described on June 27, 1980.

Witnesses: R. Orton
G. Orton
D. Allen



Office of..... County Surveyor..... County of..... Umatilla
Oregon
State of..... I hereby certify that the within instrument was filed in this office for record on the..... day of..... December, 1980
David B. Sumner by *Betty Skatts*
(COUNTY OFFICIAL) (DEPUTY)

R-187-B