

USDA-FOREST SERVICE

Index File No. C-18

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

T 5S R. 33½ E

R.D. Ukiah

County Umatilla

Tract or Survey No. _____


Cor. No. CW 1/16

Merid. Willamette

N.F. Umatilla

State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

No corner was originally set.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None set.

PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At. _____

Object Ident. _____

Ident. By _____

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner falls 65' East and 55' South of old fence corner for W, S & N fences, at East edge of large open area on top of knoll. Take U.S.F.S. Road to Frazier Camp ground south about 1/4 mile and walk west approximately 250 feet.

Title

Division
ORLS

Headquarters
1294

Date
9/77


7100-52-(3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

T5S R33 $\frac{1}{2}$ E
W $\frac{1}{16}$

At surveyed point set 2½"x30" galvanized pipe with brass cap stamped:



Set pipe 16" in ground to rock with mound of stone to cap.

1980

OR PLS 1294 9

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

Bearing Trees:

A P. Pine 23" dia. bears N66°E, 32.8 ft., scribed CW 1/16 S2BT.

A P. Pine 8" dia. bears N7°W, 83.4 ft., scribed CW 1/16 S2 BT.

Attached 54-3 and 54-4 signs to both BTs. Attached brass washer stamped LS 1294 to foot blaze of both BTs. Painted blazes and 6" band around both BTs. red. Attached 54-2, 54-4 and 54-9 signs to metal post 5' south of corner.

10

Work Done By R.C. Oregon Title Party Chief Date 6/27/80 State Registration No. or Agency _____

Certified Cor. Record Prepared? Yes No Filed At: _____ Date _____ 11

REMARKS

Witnesses: R. Orton.
G. Orton
D. Allen

12

Index File No. C-18 T. 55 R. 33 1/2 E M. _____ Tract or Surv. No. _____ U.S. G.P.O. 1977-725-576/586 Cor. 13