

USDA-FOREST SERVICE

Index

File No. D-17

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or

Survey No. _____

Cor.

No. S 1/16

T 5S R. 33 1/2 E

R.D. Ukiah

County Umatilla


State Oregon

Merid. Willamette

N.F. Umatilla

State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

No corner was originally set.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None set.

PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At. _____

Object Ident. _____

Ident. By _____

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner falls 55 ft. South of E-W fence and 200 ft. North of Dirt Road No. 5160. Take Rd. No. 5160-2 West to location tag on South side of Road. Walk North 210 ft. to corner.

Agency Signature

[Handwritten Signature]

Title

Division

Headquarters

Date

7100-52-(3/68)

ORLS

1294

9/77

4

5

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

At surveyed point set 2½"x30" galvanized pipe with brass cap stamped:

Set pipe 24" in ground with mound of stone to cap.

T5S 33½E

S 1
16

S3 + S2

1980

OR PLS 1294

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

Bearing Trees:

A Tamarack 10" dia., bears S23°E, 59.9 ft., scribed S 1/16 S2 BT.

A Tamarack 16" dia., bears N75°W, 36.8 ft., scribed S 1/16 S3 BT.

Attached 54-3 and 54-4 signs to both BTs. Attached brass washer stamped LS 1294 to foot blaze of both BTs. Painted blazes and 6" band around both BTs Red. Attached 54-2, 54-4 and 54-9 signs to metal post 5 ft. East of corner.

10

Work Done By C. Orton Title Party Chief Date 7/8/80 State Registration No. or Agency _____

Certified Cor. Record Prepared ? Yes No Filed At: _____ Date _____

11

REMARKS

Witnesses: R. Orton
D. Allen
L. Huntsman

Index File No.

D-17

T5S

R 33½E

M Willamette

Tract or Surv. No.

Cor. U.S. G.P.O. 1977-725-576/586

12

13