


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

E-5

History of original corner establishment:

Corner was originally established by Rufus S. Moore, U.S. Deputy Surveyor, under Contract No. 451, dated June 12, 1882. Surveyor General records state: Set a basalt stone 13 X 12 X 6 - 9 ins. in ground for corner to secs. 5, 6, 7, & 8, marked with 5 notches on the S and E edges, from which:
 A tamarack 15 ins in dia bears N 53° E 25 lks. dist. marked. T5S R34E S5 BT.
 A tamarack 20 ins in dia bears N 45° W 78 lks. dist. marked. T5S R34E S6 BT.
 A tamarack 24 ins. dia bears S 65° W 6 lks. dist. marked. T5S R34E S7 BT.
 A tamarack 32 ins. dia bears S 64° E 62 lks. dist. marked. T5S R34E S8 BT.



Description of corner evidence found:

A 16" western larch snag bears S 64° E- 62 links(40.9 feet), with open blaze and visible scribing.
 A 22" broken down western larch snag bears N 45° W- 78 links(51.5feet), with blaze lying on the ground in front of rotten stump.

Re-established corner by distance-distance intersection from the existing bearing tree remains.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set a 2½"X30" aluminum pipe with 2½" aluminum cap, 24" in ground and surrounded with a mound of stone to cap, marked as shown in corner diagram.

Attached sign 54-9 to steel fence post, set 4.0 feet North of monument.

New bearing trees established:

A 9½" western larch bears N 10½° W - 57.3 feet, scribed: T5SR34ES6 BT.
 A 13" western larch bears N 11° E - 36.2 feet, scribed: T5SR34ES5 BT.
 A 20" white fir bears S 52° E - 50.0 feet, scribed: T5SR34ES8 BT.
 A 14" white fir bears S 57° W - 37.5 feet, scribed: T5SR34ES7 BT.

New bearing trees have a brass washer stamped 'PLS 1106' nailed to face of blaze. Attached sign 54-3 & 54-9, painted face of blaze & a 6" red band around each bearing tree.

I hereby certify that the above corner was properly re-monumented to U.S.F.S standards by me on October 22, 1993.

Compass declination 18° East.

| |
|---|
| REGISTERED PROFESSIONAL LAND SURVEYOR |
|---|

William R. Wells

| |
|---|
| OREGON JULY 22, 1977 WILLIAM R. WELLS 1106 |
|---|

renews 12-31-94

Office of..... County Surveyor..... County of..... Umatilla.....
 State of..... Oregon....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....
 by
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
 Umatilla County Surveyor
 Date 8-4-94
 Rec'd By KK
 No. 94-106-C