


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

E-7

History of original corner establishment:
Corner was originally established by Rufus S. Moore,
U.S. Deputy Surveyor, under Contract No. 451,
dated June 12, 1882. Surveyor General records state:
Set a basalt stone 14 X 12 X 7 10 ins. in ground
for 1/4 sec. cor. marked 1/4 on W. face. from which:
A pine 5 ins. in dia. bears N 41° W 16 lks. dist.
marked 1/4 S BT.
A pine 4 ins. in dia. bears S 58° W 43 lks. dist.
marked 1/4 S BT.



Description of corner evidence found:

None. Re-established corner by single proportionate method between the Northwest and Northeast corner of Section 8.

Corner area was searched for a total of 5 hours on 3 separate occasions with a 2 person crew. 2 1/2 hours of professional land surveyor search time was spent. A search radius of ±150 feet was covered. The corner area burnt many years ago and has been logged.

Description of monument and accessories established to perpetuate the original location of this corner:

At a position determined by survey..

Set a 2 1/2"X30" aluminum pipe with 2 1/2" aluminum cap, 24" in ground and surrounded with a mound of stone to cap, marked as shown in corner diagram.

Attached sign 54-9 to steel fence post, set 4.0 feet East of monument.

New bearing trees established:

- A 23" western larch bears N 8 1/2° E - 18.8 feet, scribed: 1/4S5 BT.
A 21" western larch bears N 56° W - 22.6 feet, scribed: 1/4S5 BT.
A 12" western larch bears S 81 1/2° W - 19.2 feet, scribed: 1/4S8 BT.
A 14" western larch bears S 36° W - 20.0 feet, scribed: 1/4S8 BT

New bearing trees have a brass washer stamped 'PLS 1106' nailed to face of blaze. Attached sign 54-3 & 54-9, painted face of blaze & a 6" red band around each bearing tree.

I hereby certify that the above corner was properly re-established to U.S.F.S standards by me on October 21, 1993.

Compass declination 18° East.

REGISTERED PROFESSIONAL LAND SURVEYOR

William R. Wells

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Office of County Surveyor Umatilla County of Umatilla
State of Oregon, I hereby certify that the within instrument was filed in this office
for record on the day of 1994
renews 12-31-94
(COUNTY OFFICIAL) by (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor
Date 8-4-94
Rec'd By AK
No. 94-106-C
2