

History of original corner establishment:


Corner was established in 1882, by Rufus S. Moore, under General Land Office Contract No. 451. Surveyor General's records state: Set a basalt stone 24" x 15" x 6", 18" in ground for corner to Sec's. 4, 5, 8, & 9 marked T 5 S S 4 on NE, R 34 E S 5 on NW, S 8 on SW and S 9 on SE faces with 5 notches on S and 4 notches on east edges, from which:

A pine 60" dia. bears S 51 E, 23 lks. dist. marked T 5 S R 34 E S 9 BT.

A pine 5" dia. bears S 31 W, 60 lks. dist. marked T 5 S R 34 E S 8 BT.

A pine 20" dia. bears N 74 W, 66 lks. dist. marked T 5 S R 34 E S 5 BT.

A pine 24" dia. bears N 70 E, 55 lks. dist. marked T 5 S R 34 E S 4 BT.



Description of corner evidence found:

At the assumed corner location I found a rough basalt stone 24" x 15" x 6" lying on the surface. Stone was so rough that I could not make out any marking upon its surface. Also I found:

A pine approx. 70" dia. bears S 51 E, 23 lks. dist. with a healed blaze.

A pine approx. 8" dia. dead and on the ground with portion of stump which bears S 31 W, 60 lks. dist. and marked faintly T 5 S R 34 E S 8 BT.

A pine approx. 30" dia. bears N 74 W, 66 lks. dist. marked T 5 S R 34 E S 5 BT.

A pine approx. 32" dia. bears N 70 E, 55 lks. dist. with a healed blaze.

Description of monument and accessories I established to perpetuate the original location of this corner:

As the evidence in the vicinity of the corner agrees with the GLO original record, at the location of the found stone, I set a 2 1/2" brass cap on a 30" galv. iron pipe, and being stamped as shown above, with a large mound of stone and dirt around and of which buried the monument.

New bearing tree:

A pine 11" dia. bears S 32 W, 19.77 feet scribed T 5 S R 34 E S 8 BT.

All the remaining original bearing trees are alive and in good condition.

I hereby certify the above corner monument was re-established as herein described in August 1978.

Witnesses: James E. Green Crew Chief
L. D. Shiber Instrument Man

REGISTERED
PROFESSIONAL
LAND SURVEYOR

James H. Hambleton
8-21-78

OREGON
JULY 10, 1964
JAMES H. HAMBLETON
645

Office of..... County of.....
 State of....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....
 by
 (COUNTY OFFICIAL) (DEPUTY)