

USDA-FOREST SERVICE

Index File No. E-9


CORNER RECORD (SEARCH)
(Ref. FSM 7151.4)

Tract or Survey No. _____ Cor. No. Sec. Cor.

T 5 S R. 34 E
Merid. Willamette

R.D. LaGrande County Union
N.F. WW-16 State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

Found rough basalt stone 24" x 15" x 6" lying on surface of ground.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

70" pine bears S 51 E, 23 lks. w/healed blaze (Old BT)
8" pine dead and on ground w/portion of stump bears S 31 W, 60 lks. mkd. faintly T 5 S R 34 E S 8 BT.
30" pine bears N 74 W, 66 lks. mkd. T 5 S R 34 E S 5 BT. (old BT)
32" pine w/healed blaze bears N 70 E, 55 lks. (old BT)

PHOTO IDENTIFICATION DATA

Photo No. _____
Filed At. _____
Object Ident. _____
Ident. By _____
Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Approx. 650 ft. N of road to Blarney Springs.

PLANE COORDINATE POSITION DATA

State _____ Zone _____
X _____
Y _____
Estab. By _____
Agency

Signature
Hamberton

Title

Division
ORLS

Headquarters
615

Date
8-78

7100-52-(3/68)

CORNER RECORD (PERPETUATION)

G.P.O. 9

MONUMENT - DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 2½" x 30" iron pipe w/brass cap mkd.:
Buried in large mound of stone and dirt.

T 5 S

S 5	S 4
S 8	S 9
R 34	E
1978	

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

11" pine bears S 32 W, 1977 feet scribed T 5 S R 34 E S 8 BT. w/signs
Painted blaze and band on BT's red & yellow.
Set steel fence post by mound of stone w/signs 54-4&5.

ORLS 645
54-3&4.

Work Done By J. Hambleton Title Surveyor Date 8-78 State Registration No. ORLS 645
or Agency
Certified Cor. Record Prepared? Yes No Filed At: Union CS Date

REMARKS

Witnesses: L. Green
L. Shirley

Index File No.

T.

R.

M.

Tract or Surv. No.

Cor.