


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

H-8

History of original corner establishment:

None. Corner established as part of this survey.



Description of corner evidence found:

None.

Description of monument and accessories established to perpetuate the original location of this corner

At position established by survey...

Set a 2½" aluminum cap on 2½"x30" aluminum pipe 10" in ground surrounded with mound of earth. Set steel fence post 3.8' East of corner & attached sign 54-9 & 54-2.

New bearing trees established:

- A 12" ponderosa pine brs S32°E, 75.4' scribed SE1/16S8 BT.
- A 27" ponderosa pine brs N78°W, 138.5' scribed SE1/16S8 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 & 54-9, painted face of blaze & a 6" red band around each bearing tree.

Compass declination 18° East.

I hereby certify that the above corner was properly established to U.S.F.S. standards by me on October 28, 1993.

REGISTERED PROFESSIONAL LAND SURVEYOR

William R. Wells

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

renews 12-31-94

Office of County Surveyor County of Umatilla
 State of Oregon I hereby certify that the within instrument was filed in this office
 for record on the day of; 19....., at o'clockm., (signed)
 by
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Surveyor
 Date 8-4-94
 Rec'd By AK
 No. 94-106-C
 5