


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

None. Corner established as part of this survey.

J-8



Description of corner evidence found:

None.

Description of monument and accessories established to perpetuate the original location of this corner

At position established by survey...

Set a 2 1/2" aluminum cap on 2 1/2"x30" aluminum pipe 26" in ground surrounded with large stone mound. Set steel fence post 4.0' South of corner & attached sign 54-9 & 54-2.

New bearing trees established:

A 9" diam. tamarack brs N17°W, 20.2' scribed E1/16S8 BT.

A 11" diam. lodgepole pine brs S27°W, 150.0' scribed E1/16S17 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 & 54-9, painted face of blaze & a 6" red band around each bearing tree.

Compass declination 18° East.

I hereby certify that the above corner was properly established to U.S.F.S. standards by me on October 28, 1993.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Will: R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 12-31-94*

Office of County Surveyor County of Umatilla  
State of Oregon, I hereby certify that the within instrument was filed in this office  
for record on the        day of       ; 19      , at        o'clock        m., (signed)  
..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Surveyor

Date 8-4-84

Rec'd By KK

No. 94-106-C