


Index
 File No. J-8
T 5 S R 34 E
 Merid. Willamette

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

R.D. La Grande County Union Tract or Survey No. _____ Cor. No. _____
 N.F. Wallow-Whitman State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

None. Corner established as part of this survey.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None.

PHOTO IDENTIFICATION DATA

Photo No. _____
 Filed At. _____
 Object Ident. _____
 Ident. By _____

Signature

7

PLANE COORDINATE POSITION DATA

State _____ Zone _____
 X _____
 Y _____
 Estab. By _____

Agency

8

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner is in West edge of opening at West edge of meadow approx. 900' East of Road No. 5160.

Signature

Wall R. Wells

Title

Land Surveyor

Division

Headquarters

Pendleton, OR,

Date

10-28-93

FS-7100-52 (3/68)

5

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

At position established by survey...

Set a 2 1/2" aluminum cap on 2 1/2"x30" aluminum pipe 26" in ground surrounded with large stone mound. Set a steel fence post 4.0' South of corner & attached sign 54-9 & 54-2.

Compass declination 18° East.

9

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

New bearing trees established:

A 9"diam. Western Larch brs. N17°W, 20.2'scribed El/16S8 BT.

A 11"diam. lodgepole pine brs S27°W, 150.0'scribed El/16S17 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 & 54-9, painted face of blaze & a 6" red band around each BT.

10

Work Done By W.R. Wells Title Land Surveyor Date 10-28-93 State Registration No. PLS 1106
or Agency

Certified Cor. Record Prepared ? Yes XXXX Filed Unatilla County Surveyor Date 8/94

11

REMARKS

Index File No. J-8 T. 5 S. R. 34 E. WM.M. Tract or Surv. No. Cor. 13