


History of original corner establishment:

The original corner was set by J. Cooper under Contract No. 397, approved April 5, 1882. He set two bearing trees: a 10" Pine bearing N36°W, 80 lks. and a 27" Pine bearing N50°E, 30 lks.



Description of corner evidence found:

Found 3.5" BLM brass cap rising 14" on 2.5" iron pipe. Cap is stamped:

Bearing trees found:

- A 13" P. Pine bears S73°E, 34.0 ft., scribed (1/4 S18 BT).
- A 16" P. Pine bears N18°W, 52.8 ft., scribed (1/4 S) healed over.

T5S
1/4
R33 1/2E | R34E
S13 | S18
1977

Description of monument and accessories established to perpetuate the original location of this corner:

Raised rock mound around cap. Set steel fence post 4.0 ft. north.

Brass LS 1844 disc in lower end of blaze. Painted blazes and attached signs as per Standard Specifications for Cadastral Surveys, USFS Region 6, March 1982.

Compass Declination: 19 3/4°E Witness: Duane Scott

Corner is found 100 ft. east of dirt tract in clearing, reached from end of Road 5160-361.

I hereby certify the above described corner monument and/or accessories was established in June of 1984.



L-1

Office of..... County of.....
 State of..... I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....
 by
 (COUNTY OFFICIAL) (DEPUTY)

93-39-B