


Index
File No. 2-15
T 5 S R. 34 E
Merid. Willamette

CORNER RECORD (SEARCH)
(Ref. FSM 7151.4)
R.D. LaGrande County Union
N.F. WW-16 State Oregon

Tract or
Survey No. _____
Cor.
No. C 1/4

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

None

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None

PHOTO IDENTIFICATION DATA

Photo No. _____
Filed At. _____
Object Ident. _____
Ident. By _____
Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____
X _____
Y _____
Estab. By _____
Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Approx. 250 ft. E of Squaw Creek in large meadow.

Signature
Hambleton

Title _____ Division **ORLS** Headquarters **645**

Date
8-78

7100-52-(3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 2 $\frac{1}{2}$ " x 30" iron pipe w/brass cap mkd.:
Large mound of stone around monument.

T 5 S
C 1/4
S 15
R 3/4 E
1978
ORLS 645

9

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

5" pine bears S 32 W, 21.75 ft. scribed $\frac{1}{4}$ S S15 BT.
5" pine bears S 87 E, 7.25 ft. scribed $\frac{1}{4}$ S S15 BT.
Painted blaze and band of BT's red & yellow. Tagged trees w/54-3&4 signs.
Set steel fence post by mound of stone w/signs 54-4, 6&9.

10

Work Done By J. Hambleton Title Surveyor Date 8-78 State Registration No. or Agency Orls 645
Certified Cor. Record Prepared? Yes No Filed At: Union CS Date _____

11

REMARKS

Witnesses: L. Green
L. Shirley

12

Index File No. T. R. M. Tract or Surv. No. Cor. 13