

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 05/15/01

CORNER DESIGNATION: R-9

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Nicholas O. Walden, U.S. Dept. Surv., under Contract No. 209, dated July 6, 1874. Record states: Set basalt stone 15 x 8 x 6, 8 ins. in ground, for Cor. to Secs. 20, 21, 28 & 29.

Geary Kimbrell, Deputy County Surveyor, claims to have recovered this corner during Survey No. 239, dated March, 1906, but does not state what was found.

MONUMENT AND ACCESSORIES FOUND: Found a 15" x 8" x 6" set stone with 2 grooves North side and 4 grooves on East side.

MONUMENT MARKING DETAIL:

T6N R33E
S20 | S21
S29 | S28
2001
PLS 1106

MONUMENT SET:

At position of found original stone, set a 2 1/2" aluminum cap on a 2 1/2" x 30" aluminum pipe with top 2" above ground. Buried original stone, with grooves visible on South side of New monument. Monument marked as shown in "Monument Marking Detail".

From which:

- A 5/8" x 30" iron rebar with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears N 25 1/2° E, 20.6 feet.
- A 5/8" x 30" iron rebar with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears S 53 1/2° E, 35.8 feet.
- A 5/8" x 30" iron rebar with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears S 40° W, 16.4 feet.
- A 5/8" x 30" iron rebar with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears N 55 1/2° W, 29.7 feet.

Wired bearing object tags to 5/8" iron rebar accessories. Set steel fence post with "witness" sign attached, North of new monument.

LOCATION AND COMMENTS: Corner is located on steep, North facing hillside with no nearby features.

OREGON STATE PLANE CO-ORDINATES, OREGON NORTH, NAD83(91): *fti*

N: 848224.63

E: 8658564.36

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT
Mark Hammersla

\6N33R9

Surveyor's Seal

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

William R. Wells

OREGON
 JULY 22, 1977
 WILLIAM R. WELLS
 1106

renews 6-30-02

RECEIVED BY
 Umatilla County Surveyor
 Date 9-01
 Rec'd By AK
 No. 01-139-C