

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 04/29/09

CORNER DESIGNATION: T-11, The Center One-Quarter Corner of Section 28, Township 6 North, Range 33 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Geary Kimbrell under Survey No. 239, dated March, 1906. Kimbrell's notes indicate he set a stone for the Center one-quarter corner after recovering opposite one-quarter corners and intersecting "right-lines".

MONUMENT AND ACCESSORIES FOUND: Found and held stone mound in ancient North-South fence line. These stones are the only ones in the corner vicinity.

MONUMENT MARKING DETAIL:

T6N R33E
C 1/4 S28
2009
PLS 1106

MONUMENT SET: At the center of the found stone mound, set a 2 3/8" diameter brass cap on a 1 1/4" x 30" galvanized iron pipe, 30" in the ground, marked as shown in "Monument Marking Detail".

New accessories:

A 1 1/4" red plastic cap marked "OR PLS 1106, WA PLS 17372", on a 5/8" by 30" rebar, bears North 47° East, a distance of 15.1 feet.

A 1 1/4" red plastic cap marked "OR PLS 1106, WA PLS 17372", on a 5/8" by 30" rebar, bears South 42 1/2° East, a distance of 14.5 feet.

A blue Deep-1 magnet bears South 47° West, a distance of 13.6 feet, buried 12 inches.

An orange Deep-1 magnet bears North 42° West, a distance of 12.7 feet, buried 12 inches.

Rebar accessories have bearing object signs attached. Set steel fence post 3 feet North of corner with witness sign.

LOCATION AND COMMENTS: Corner falls in ancient North-South fence remains.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 845593.08
E = 8661295.31

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Matt Brockamp
D. Palmer

\6N33T11

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-10