

OREGON CORNER RESTORATION FORM

Section: 26
Township: 6N
Range: 34 EWM
County: Umatilla
Date: 12/30/99
Corner Designation: V-21

Previous Renewals/Surveys, etc.: Original GLO corner established as a post, with pits and mounds, by Odell, under contract No. 110, in 1865. Survey 98-108-b by Bartleson in 1998 shown found fence corner post.

Monument(s) & Accessories Found (Condition & Source: Found old fence corner to North, South and West as shown on Survey 98-108-b.

Monument Detail: Set 1" iron pipe topped with 2 1/2" brass cap, stamped as shown:

T6N
26 | 25
+
35 | 36
R34E
1999
LS 2360

Monument Set (Procedures & Description):

Set pipe along East side of fence corner post.

New Accessories:

We set:

A 5/8" rebar w/ yellow cap stamped 'Tomkins Surveying' which bears East 10.0' from the corner.

A 5/8" rebar w/ yellow cap stamped 'Tomkins Surveying' which bears South 14.1' from the corner, and attached B.O. tag to fence post.

A 5/8" rebar w/ yellow cap stamped 'Tomkins Surveying' which bears West 10.0' from the corner, and attached B.O. tag to fence post.

A 5/8" rebar w/ yellow cap stamped 'Tomkins Surveying' which bears North 21.1' from the corner, and attached B.O. tag to fence post.

Location & Comments:

The corner falls at existing fence corner post on flat land.



Compass Declination:

19° East Dec. used to tie B.O.'s.

Firm/Agency: Paul Tomkins Land Surveying
20 E. Poplar Ste. 204
Walla Walla WA 99362

Party Chief: Thomas S. Butler
Notes: Thomas S. Butler
Witness: Brianna Slater

Surveyor's Seal



2/18/00

00-31-B