

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 04/25/08

CORNER DESIGNATION: L-25, The East One-Corner Quarter of Section 13, Township 6 North, Range 36 East, W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner was originally established by Odell & Lewis under GLO Contract No. 110, dated February 7, 1865. Notes state: Set 1/4 Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T6N  
1/4  
R36E R37E  
S13|S18  
2008  
PLS 1106

MONUMENT SET: Reestablished corner by single proportionate measure between the Northeast and Southeast Corners of Section 13. A reestablished corner point, set a 2 3/8" brass cap on a 1 1/4" x 20" galvanized iron pipe with cap buried 18" below ground level, marked as shown in "Monument Marking Detail". (Hit rock and had to shorten monument to get the bury).

New accessories:

- A silver deep-1 magnet bears North 52 1/2° East, 32.8 feet.
- A purple deep-1 magnet bears South 50 1/2° East, 44.8 feet.
- A 5/8" x 24" rebar with red plastic cap marked "OR PLS 1106 WA PLS 17382 bears South 38° West, 93.7 feet.
- A 5/8" x 24" rebar with a red plastic cap marked "OR PLS 1106, WA PLS 17372" bears North 88° West, 119.6 feet.
- Deep-1 magnets are buried 20 inches below ground level with bearing object signs. Rebar accessories have bearing object signs attached.

LOCATION AND COMMENTS: Corner falls in wheat field, no features nearby, except for old fence along the edge of field to the West.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 858130.31  
E = 8774873.70

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells, LSIT

\6N36L25

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*Expires 6-30-10*

*09-10-c*