

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla. DATE: 07/29/08

CORNER DESIGNATION: L-5, the East One-Quarter Corner of Section 18, Township 6 North, Range 36 East, W.M..

PREVIOUS RENEWALS/SURVEYS ETC: Corner originally set by Odell & Lewis under GLO Contract No. 110, dated February 7, 1865. Notes state: Set 1/4 Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. Falls in wheat field with no nearby features.

**MONUMENT MARKING DETAIL:**

T6N R36E  
1/4  
S18 | S17  
2008  
PLS 1106

MONUMENT SET: Reestablished corner position by single proportionate measure between the reestablished Southeast Corner and Northeast Closing Corner of Section 18. At the reestablished corner point, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe, with cap buried 22" below ground level, marked as shown in "Monument Marking Detail".

**New accessories:**

- A silver deep-1 magnet bears North 51° East, 29.0 feet.
- A purple deep-1 magnet bears South 45° East, 36.9 feet.
- An irrigation riser bears North 01° East, 118.8 feet.
- An irrigation riser bears South 07° West, 59.9 feet.
- Deep-1 magnets are buried 20" below ground level with bearing object signs. No bearing object signs were placed on irrigation risers.

LOCATION AND COMMENTS: Corner is about 5 feet East of a North-South line of irrigation risers, in a wheat field, with no nearby features.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 857349.73  
E = 8748220.14


FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East


Surveyor's Seal

Witnesses: Jason Wells, LSIT

\6N36L5



*William R. Wells*



*Renews 6-30-10*