

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla. DATE: 04/25/08

CORNER DESIGNATION: N-11, The North Quarter Corner of Section 21, Township 6 North, Range 36 East, W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally set by Odell & Lewis under GLO Contract No. 110, dated February 7, 1865. Notes state: Set 1/4 Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. Corner falls in wheat field.

MONUMENT MARKING DETAIL:

T6N R36E  
1 S16  
4 S21  
2008  
PLS 1106

MONUMENT SET: Corner point was reestablished by single proportionate measure between the accepted Northwest and Northeast Corners of Section 21. At the reestablished corner point, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe, with cap buried 20" below ground level, marked as shown in "Monument Marking Detail".

New accessories:

- A silver deep-1 magnet bears North 15° East, 32.3 feet.
- A purple deep-1 magnet bears South 66° East, 30.5 feet.
- A blue deep-1 magnet bears South 23° West, 27.6 feet.
- An orange deep-1 magnet bears North 65° West, 29.5 feet.
- Buried deep-1 magnets 20" below ground level, with bearing object signs.

LOCATION AND COMMENTS: Corner falls in a farmed field no nearby features, about 300 feet West of a gully.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 854821.42  
E = 8756226.77

FIRM: Wells, Surveying  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

\6N36N11

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Will. R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*Renews 6-30-10*