

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 04/04/08

CORNER DESIGNATION: N-15, The South Quarter Corner of Section 15, Township 6 North, Range 36 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Odell & Lewis under GLO Contract No. 110, dated February 7, 1865. Notes state: Set 1/4 Sec. post. Drove chared stake; dug pits & raised mound, as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. Corner point at intersection of East-West and North-South field lines.

MONUMENT MARKING DETAIL:

T6N R36E	
<u>1</u> S15	Note: the cap is actually marked <u>1</u> S23
4 S22	4 S26
2008	
PLS 1106	

MONUMENT SET: Held the intersection of field berm East-West with a field lines North and South as best remaining evidence of the original corner location. At the reestablished corner point, set a 2 3/8 brass cap on a 1 1/4" x 30" galvanized iron pipe, with cap buried 18" below ground level, marked as shown on "Monument Marking Detail".

New accessories:

A 3/4" brass washer stamped "PLS 1106" on South side of a sawed of power pole, 1 foot above ground level bears North 01 1/2° East, 67.8 feet. Attached bearing object sign and witness post sign to sawed off power pole.

A 3/4" brass washer stamped "PLS 1106" 1 foot above ground level in West side of power pole, bears South 88° East, 141.4 feet, with bearing object sign attached.

A purple deep-1 magnet bears South 12° East, 36.9 feet.

A blue deep-1 magnet bears South 56 1/2° West, 41.2 feet.

Deep-1 magnets are buried 20 inches below ground level with bearing object signs.

LOCATION AND COMMENTS: Located at the intersection of a field berm extending East and West and North and South. There are remains of woven wire fence wrapped around sawed off power pole North 01 1/2° East of corner. An active power pole line runs along the East and West field berm.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 855014.50

E = 8761546.54

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Wells Surveying
Jason Wells, LSIT

\6N36N15

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will. R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6-30-10