

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla. DATE: 04/16/08

CORNER DESIGNATION: N-23, The South One Quarter Corner of Section 13, Township 6 North, Range 36 East, W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Odell & Lewis under GLO Contract No. 110, dated February 7, 1865. Notes state: Set 1/4 Sec Post. Drove charred stake. Dug pits and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

**MONUMENT MARKING DETAIL:**

T6N R36E  
1 S13  
4 S24  
2008  
PLS 1106

MONUMENT SET: Reestablished by single proportion measure between the Northeast and Northwest Corners of Section 24. At the reestablished corner point, set a 2 3/8" brass cap monument on a 1 1/4" x 20" galvanized iron pipe, with cap 22" below ground surface, marked as shown in "Monument Marking Detail".

New accessories:

- A silver deep-1 magnet bears North 62° East, 30.2 feet.
  - A purple deep-1 magnet bears South 41 1/2° East, 31.2 feet.
  - A blue deep-1 magnet bears South 53° West, 29.9 feet.
  - An orange deep-1 magnet bears North 20° West, 25.3 feet.
- Deep-1 magnets are buried 20" below ground level with bearing object signs.

LOCATION AND COMMENTS: No nearby features, falls in wheat field.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 855418.23  
E = 8772240.83

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

\6N36N23

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*Expires 6-30-10*