

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 04/16/08

CORNER DESIGNATION: P-25, The East One-Quarter Corner of Section 24, Township 6 North, Range 36 East, W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner was originally established by Odell & Lewis under GLO Contract No. 110, dated February 7, 1865. Notes State: Set 1/4 Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T6N
R36E R37E
1/4
S24 | S19
2008
PLS 1106

MONUMENT SET: Corner point was reestablished by single proportion measure between the Northeast Corner of Section 24 and the accepted Southeast Corner of Section 24. At reestablished corner point, set a 2 3/8" brass cap on a 1 1/4" x 20" galvanized iron pipe, with cap buried 20" below ground level, marked as shown in "Monument Marking Detail".

From which:

- A silver deep-1 magnet bears North 56 1/2° East, 28.6 feet.
 - A purple deep-1 magnet bears South 24 1/2° East, 32.3 feet.
 - A blue deep-1 magnet bears South 58° West, 33.9 feet.
 - An orange deep-1 magnet bears North 40 1/2° West, 31.4 feet.
- Deep-1 magnets are buried 20" below ground level with bearing object signs.

LOCATION AND COMMENTS: Corner falls in wheat field, there are no nearby features. The Southeast Corner of Section 24 was reestablished by Bartleson under Survey No. 99-282-B. I accepted this monument as the corner because it fits nearby features such as the road centerline North. I did not accept monuments from Survey No. 99-282-B at the Northeast Corners of Sections 13 and 24. See Land Corner Records for those corners.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 852878.61
E = 8774985.48

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

√6N36P25

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Expires 6-30-10