

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 03/05/08

CORNER DESIGNATION: P-9, the East One-Quarter Corner Section 20, Township 6 North, Range 36 East, W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes State: Set 1/4 Sec. pot. Drove charred stake; dug pits & raised mound, as per instructions.

J. H. Raley, County Surveyor, recovered this corner in survey recorded in Book 1, Page 51, Record of Private Surveys. Raley does not state what was found for the corner.

Don Staebler did not recover this corner and calculated a position for it, mid-way between the Northeast and Southeast Corner of Section 20 in Survey No. K-79-B, in 1974.

MONUMENT AND ACCESSORIES FOUND: None. Corner falls in North-South field berm.

MONUMENT MARKING DETAIL:

T6N R36E
1/4
S20 | S21
2008
PLS 1106

MONUMENT SET: Corner point was reestablished by single proportionate measure between the recovered and accepted Northeast and Southeast Corners of Section 20. At the reestablished corner point, set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe with cap buried 18" below ground level, marked as shown in "Monument Marking Detail".

New accessories:

- A silver deep-1 magnet bears North 48 1/2° East, 26.9 feet.
 - A purple deep-1 magnet bears South 50 1/2° East, 24.9 feet.
 - A blue deep-1 magnet bears South 42 1/2° West, 38.2 feet.
 - An orange deep-1 magnet bears North 41° West, 34.2 feet
- All deep-1 magnets are buried 22" below ground level with bearing object signs.

LOCATION AND COMMENTS: Falls in North-South berm, between farmed fields.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 852200.89
E = 8753662.72

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

\6N36P9

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6-30-10