

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 07/29/08

CORNER DESIGNATION: R-11, The North One-Quarter Corner of Section 28, Township 6 North, Range 36 East, W.M..

PREVIOUS RENEWALS/SURVEYS ETC: Corner originally set by Odell & Lewis under GLO Contract No. 110, dated February 7, 1865. Notes state: Set 1/4 Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. Corner falls in the centerline of paved Birch Creek Road.

MONUMENT MARKING DETAIL:

T6N R36E
1 S21
4 S28
2008
PLS 1106

MONUMENT SET: I held the centerline of Birch Creek Road for latitude. For departure, I proportioned against the Odell and Lewis record between the recovered Northeast and northwest Corners of Section 28. At the reestablished corner position, set a 2" brass cap on a 12" copper clad bar with brass cap 1/4" below asphalt pavement, and surrounded with grout. Cap is marked as shown in "Monument Marking Detail".

New accessories:

A 5/8" x 24" rebar with a red plastic cap marked "OR PLS 1106, WA PLS 17372", bears North 50° East, 26.8 feet.

A 5/8" x 24" rebar with a red plastic cap marked "OR PLS 1106, WA PLS 17372", bears South 39° East, 31.9 feet.

A 3/4" brass washer stamped "PLS 1106", on a power pole, 1' above ground level, bears South 62 1/2° West, 46.7 feet, with bearing object and witness sign attached to pole.

A 5/8" x 24" rebar with a red plastic cap marked "OR PLS 1106, WA PLS 17372", bears North 36° West, 26.2 feet.

Attached bearing object signs to all rebar accessories.

LOCATION AND COMMENTS: Corner is located in the centerline of paved Birch Creek Road.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 849664.94

E = 8756396.01


FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East


Surveyor's Seal

Witnesses: Jason Wells, LSIT

6N36R11



William R. Wells



Renews 6-30-10