

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 03/05/08

CORNER DESIGNATION: T-13, The East One-Quarter Corner of Section 28, Township 6 North, Range 36 East, W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner was originally established by Odell & Lewis under GLO Contract No. 110, dated February 7, 1865. Notes state: Set 1/4 Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.

John Kimbrell, in his survey recorded at Book 1, Page 401, Record of Private Surveys, surveyed through the corner area but did not recover or reestablish the corner.

MONUMENT AND ACCESSORIES FOUND: None. Falls in wheat field about 250 feet North of a gulch.

MONUMENT MARKING DETAIL:

T6N R36E
1/4
S28 | S27
2008
PLS 1106

MONUMENT SET: Corner point was reestablished by single proportionate measure between the accepted Northeast and Southeast corners of Section 28. At the reestablished corner point set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe, with cap 18" below ground level, marked as shown in "Monument Marking Detail".

New accessories:

- A silver deep-1 magnet bears North 48° East, 32.0 feet.
- A purple deep-1 magnet bears South 37 1/2° East, 35.0 feet.
- A blue deep-1 magnet bears South 61 1/2° West, 35.5 feet.
- An orange deep-1 magnet bears North 43 1/2° West, 32.4 feet.
- All deep-1 magnets are buried 22" below ground level with bearing object signs.

LOCATION AND COMMENTS: Corner falls in wheat field, farmed all around, with no nearby features. There is a gulch about 250 feet South of corner.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 847067.72
E = 8759209.73

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

6N36T13

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Expires 6-30-10

09-10-e