

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla. DATE: 04/10/08

CORNER DESIGNATION: T-21, The East Quarter Corner of Section 26, Township 6 North, Range 36 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Odell & Lewis under GLO Contract No. 110, dated February 7, 1865. Notes state: Set 1/4 Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T6N R36E  
1/4  
S26 | S25  
2008  
PLS 1106

MONUMENT SET: Corner was reestablished on line between the Southeast and Northeast Corners of Section 26, holding old East-West field and fence line for latitude. At the reestablished corner point, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe with cap 18" below ground level, marked as shown in "Monument Marking Detail".

New accessories:

- A silver deep-1 magnet bears North 54 1/2° East, 31.8 feet.
  - A purple deep-1 magnet bears South 23 1/2° East, 31.9 feet.
  - A blue deep-1 magnet bears South 43 1/2° West, 28.8 feet.
  - An orange deep-1 magnet bears North 34 1/2° West, 27.0 feet.
- Deep-1 magnets are buried 20" below ground level with bearing object signs.

LOCATION AND COMMENTS: No nearby features other than the East-West field and old fence line.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 847371.29  
E = 8769797.50

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

\6N36T21

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Will: R. Wells*

OREGON  
JULY 27, 1977  
WILLIAM R. WELLS  
1106

*Expires 6-30-10*