

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 03/06/08

CORNER DESIGNATION: T-9, the East One-Quarter Corner of Section 29, Township 6 North, Range 36 East, W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Odell & Lewis under GLO Contract No. 110, dated February 7, 1865. Notes state: Set 1/4 Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. Corner falls in irrigated wheat field with wheat all around it.

MONUMENT MARKING DETAIL:

T6N R36E  
1/4  
29|28  
2008  
PLS 1106

MONUMENT SET: Corner point was reestablished by single proportionate measure between the accepted Northeast Corner of Section 29 and the accepted Southeast Corner of Section 29. At reestablished corner point, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe with cap buried 24" below ground level, marked as shown in "Monument Marking Detail".

New accessories:

- A silver deep-1 magnet bears North 43 1/2° East, 34.8 feet.
  - A purple deep-1 magnet bears South 39 1/2° East, 31.4 feet.
  - A blue deep-1 magnet bears South 50° West, 39.9 feet.
  - An orange deep-1 magnet bears North 38 1/2° West, 38.3 feet.
- All deep-1 magnets are buried 24" below ground level with bearing object signs.

LOCATION AND COMMENTS: Corner is located in a farmed field. No other features.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 846973.88  
E = 8753879.59

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

\6N36T9

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Will. R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

RENEWS 6-30-10

09-10-C