

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 03/12/08

CORNER DESIGNATION: V-25, The Northeast Corner of Section 36, Township 6 North, Range 36 East, W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Odell & Lewis under GLO Contract No. 110, dated February 7, 1865. Notes state: Set post Cor. For Secs. 25, 26, 30 & 31. Drove charred stake; dug pits & raised mound, as per instructions.

Survey No. 99-282-B, by Bartleson, reports a Brass Cap monument set at E-W & North fence intersection.

MONUMENT AND ACCESSORIES FOUND: Brass cap monument per Survey No. 99-282-B was not found. Found a 40 penny spike and flagging instead.

MONUMENT MARKING DETAIL:

T6N
R36E | R37E
S25 | S30
S36 | S31
2008
PLS 1106

MONUMENT SET: At the position of the found spike, which was verified by survey, against Survey No. 99-282-B, set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe with cap buried 16" below ground level, marked as shown in "Monument Marking Detail".

New accessories:

- A silver deep-1 magnet bears North 52 1/2° East, 30.9 feet.
- A purple deep-1 magnet bears South 37 1/2° East, 32.6 feet.
- A blue deep-1 magnet bears South 52 1/2° West, 33.1 feet.
- An orange deep-1 magnet bears North 49 1/2° West, 27.1 feet.
- All deep-1 magnets are buried 24" below ground level with bearing object signs.

LOCATION AND COMMENTS: Falls in field intersection with field berms East & North & field line extending West.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 844998.03
E = 8775184.71

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

\6N36V25

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 23, 1977
WILLIAM R. WELLS
1106

Expires 6-30-10

09-10-c