

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla. DATE: 03/12/08

CORNER DESIGNATION: X-21, the East Quarter One-Corner of Section 35, Township 6 North, Range 36 East, W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Odell & Lewis under GLO Contract No. 110, dated February 7, 1865. Notes state: Set 1/4 Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.

John Kimbrell, in his survey recorded at Book 1, Page 492, Record of Private Surveys, surveyed to this corner but does not state what was found.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T6N R36E  
1/4  
S35 | S36  
2008  
PLS 1106

MONUMENT SET: Held a point just South of a 6" well casing in a North-South field berm as best remaining evidence of the original corner location. At the reestablished corner point, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe, with cap flush with the ground, marked as shown in "Monument Marking Detail".

New accessories:

- A silver deep-1 magnet bears North 48° East, 36.8 feet.
  - A purple deep-1 magnet bears South 54 1/2° East, 29.2 feet.
  - A blue deep-1 magnet bears South 60 1/2° West, 46.2 feet.
  - An orange deep-1 magnet bears North 39° West, 33.3 feet.
- Deep-1 magnets are buried 24" below ground level with bearing object signs. Wired witness sign to well casing North of the corner monument.

LOCATION AND COMMENTS: Well casing stands 4 feet above ground level painted white. A field berm extends South and North from corner point. There is a field road about 25 feet South of corner.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 842111.79  
E = 8769968.58

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

\6N36X21

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*Expires 6-30-10*

*09-10-c*