

# OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 04/17/08

CORNER DESIGNATION: X-5, The East One-Quarter Corner of Section 31, Township 6 North, Range 36 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Odell & Lewis under GLO Contract No. 110, dated February 7, 1865. Notes state: Set 1/4 Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.

John Kimbrell, in his survey recorded at Book 1, Page 420, Record of Private Surveys, declared this corner lost, reestablished it and set a 20 x 10 x 8" stone.

MONUMENT AND ACCESSORIES FOUND: None. Corner falls in extensively farm fields.

## MONUMENT MARKING DETAIL:

T6N R36E  
1/4  
S31 | S32  
2008  
PLS 1106

MONUMENT SET: Corner point was reestablished by single proportionate measure between the accepted Northeast Corner of Section 31 and the reestablished Southeast Corner of Section 31. At reestablished corner point, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe, with cap buried 20" below ground level marked as shown in "Monument Marking Detail".

## New accessories:

An irrigation air release valve with two gate valves bears North 44 1/2° East, 90.0 feet, with a bearing object sign attached to it.

A purple deep-1 magnet bears South 45 1/2° East, 34.2 feet.

A blue deep-1 magnet bears South 40 1/2° West, 30.7 feet.

An orange deep-1 magnet bears North 34° West, 36.2 feet, located at the South edge of East-West field road.

Deep-1 magnets are buried 20" below ground line with bearing object signs.

LOCATION AND COMMENTS: Falls in farmed field 40' South of East-West field road at Northern edge of center pivot circle.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 841455.56

E = 8748723.69

FIRM: Wells Surveying

P.O. Box 1696


Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

\6N36X5



*William R. Wells*  
OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*Renews 6-30-10*

*09-10-C*