

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 06/17/2014

CORNER DESIGNATION: K-13, Closing Corner for Sections 15 and 16, Township 6 North, Range 37E, W.M.

PREVIOUS RENEWALS/SURVEYS ETC:

Originally surveyed by A.H. Simmons for Deputy Surveyor George Williams under his contract No. 176 dated October 23, 1872; his notes state "Set stone 6" x 9" x 13" for cor. to fractional section 15 and 16.

MOUNUMENT AND ACCESSORIES FOUND:

Found stone 11" x 12" x 8" rock with "CC 16" on one side and "CC 15" on other side amongst a pile of rocks.
A 5/8" iron rebar with a yellow plastic cap marked "Tomkins Surveying" bears N. 50° E., 15.20 ft.
The found rebar is at the base of a fence/corner post with a bearing tree tag attached.

MOUNUMENT MARKING DETAIL:

WASHINGTON
S 16 | S 15
CC
2014
02820

MOUNUMENT AND ACCESSORIES SET:

At the position of the found rock, set a 2 1/2" brass cap on a 1 1/2" x 30" galvanized iron pipe, and set original rock next to pipe, with stone mound +/- 1' from which:
A 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears N. 44° W. 16.55 ft.
A 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears S. 11° E., 16.70 ft.
A 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears S. 25° W., 26.40 ft.

LOCATION AND COMMENTS:

Corner is on a gentle sloping south facing grassy slope, approximately 15' north of a small ravine. A North-South barbed wire fence is +/- 9' to the East. A prominent cattle trail runs next to the corner. Bearings taken with Silva hand compass and distances measured with a steel tape.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 859370.53
E = 8790914.53

COMPASS DECLINATION: 15° East


SURVEYORS' SEAL:

FIRM: HDJ Design Group
5 N. Colville, Suite 200
Walla Walla WA 99362

WITNESSES: Thomas J. Boshart
Felipe G. Hernandez



Greg E. Flowers



RENEWS 12/31/15
6/29/2015

15-063-C