

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 10/29/2014

CORNER DESIGNATION: K-21, Closing Corner for Sections 14 and 13, Township 6 North, Range 37E, W.M.

PREVIOUS RENEWALS/SURVEYS ETC:

Originally surveyed by A.H. Simmons for Deputy Surveyor George Williams under his contract No. 176 dated October 23, 1872; his notes state "Intersect N. boundary of state line 15.97 chs. W. of 40 Mile Post, set post for closing corner from which a pine 10" diam., bears N 15° E., 71 chs. dist. A Pine 5" diam., bears S 6° W., 23 chs. dist.

MOUNUMENT AND ACCESSORIES FOUND:

No evidence of original corner found

MOUNUMENT MARKING DETAIL:

2014
HDJ
S 14 | S 13
T 6N R 37E
CC

MOUNUMENT AND ACCESSORIES SET:

At the surveyed position of the closing corner for sections 13 and 14, set a 2½" brass cap on a 1½" x 30" galvanized iron pipe, .5" above ground from which:
A 15" diam. fir tree bearing N. 8° W. 39.50 ft.
A 10" diam. fir tree bearing N. 76° E. 17.00 ft.
A 22" diam. fir tree bearing S. 24° E., 25.00 ft.
A 22" diam. fir tree bearing S. 32° W., 28.00 ft.

LOCATION AND COMMENTS:

Bearings taken with Silva hand compass and distances measured with a steel tape.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 859658.37
E = 8801023.94

COMPASS DECLINATION: 15° East


SURVEYORS' SEAL:

FIRM: HDJ Design Group
5 N. Colville, Suite 200
Walla Walla WA 99362

WITNESSES: Joseph R. Latimer
Corey A. West



Greg E. Flowers



RENEWS 12/31/15

6/29/2015

15-063-C