

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla **DATE:** 01/20/2015

CORNER DESIGNATION: L-13, Quarter Corner Section for Sections 15 and 16, Township 6 North, Range 37E, W.M.

PREVIOUS RENEWALS/SURVEYS ETC:

Originally surveyed by A.H. Simmons for Deputy Surveyor George Williams under his contract No. 176 dated October 23, 1872; his notes state "Set stone 12x 18 x 36 for 1/4 Sec. Cor.

MOUNUMENT AND ACCESSORIES FOUND:

No evidence found.

MOUNUMENT MARKING DETAIL:

LS 02820
T 6N R 37E
S 16 | S 15
 |
 1/4
 1/2015

MOUNUMENT AND ACCESSORIES SET:

At the surveyed position, set 2 1/2" brass cap on a 1 1/2" x 30" galvanized iron pipe 1" above ground surrounded with rock mound, with the following accessories:

- A 5/8" x 30" iron rebar with yellow plastic cap "TLS-HDJ" bears N. 42° W., 10.00 feet distance.
- A 5/8" x 30" iron rebar with yellow plastic cap "TLS-HDJ" bears N. 48° E., 7.00 feet distance.
- A 5/8" x 30" iron rebar with yellow plastic cap "TLS-HDJ" bears S. 33° E, 10.80 feet distance.
- A 5/8" x 30" iron rebar with yellow plastic cap "TLS-HDJ" bears S. 45° W., 10.70 feet distance.

LOCATION AND COMMENTS:

Bearings taken with Silva hand compass and distances measured with a steel tape.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 858541.21
E = 8790839.358

COMPASS DECLINATION: 15° East

SURVEYORS' SEAL:

FIRM: HDJ Design Group
5 N. Colville, Suite 200
Walla Walla WA 99362

WITNESSES: Joseph R Latimer
Cory A. West
Felipe G. Hernandez



Greg E. Flowers
OREGON
JUNE 30, 1997
GREG E. FLOWERS
02820LS

RENEWS 12/31/15

06/29/2015