

MOUNUMENT AND ACCESSORIES SET:

Set a 5/8 ins. x 30 ins. iron rebar with yellow plastic cap marked "TLS-HDJ" bears N. 31° W., 42.20 ft., attached bearing tag in mound of rocks +/- 1ft. from ground.

Bearing tag with mag nail in rock, bears S. 60° W., 22.70 ft.

Set a 5/8 ins. x 30 ins. iron rebar with yellow plastic cap marked "TLS-HDJ" on East/West fence line at base of existing fence T-post, bears S. 88° E., 92.30 ft.

T-post in fence line bears N 90° W., 27.10 ft., attached tag.

Set a 5/8" x 30" iron rebar, 8" above ground bears N. 38° E., 13.70 ft., set a "T" post as witness post with a bearing object tag.

LOCATION AND COMMENTS:

Located on South facing open, grassy slope. Bearings taken with Silva hand compass and distances measured with a steel tape.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 855873.06

E = 8788031.09

COMPASS DECLINATION: 15° East

SURVEYORS' SEAL:

FIRM: HDJ Design Group
5 N. Colville, Suite 200
Walla Walla WA 99362

WITNESSES: Thomas J. Boshart
Felipe G. Hernandez
Corey A. West
Timothy K. Bannister



RENEWS 12/31/15

06/29/2015

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 06/16/2014

CORNER DESIGNATION: N-11, Quarter Corner for Sections 16 and 21, Township 6 North, Range 37E, W.M.

PREVIOUS RENEWALS/SURVEYS ETC:

Originally surveyed by A. H. Simmons for US Deputy Surveyor George Williams under his contract No. 176 dated July 20, 1872. His notes state "Set stone 2 x 6 x 15 mound of stone for 1/4 Sec. Cor.

BLM Cadastral Surveyor C. Alfred White in his April 21, 1965 for Group 572, stated in his notes: "From this point the 1/4 sec. cor. of secs. 16 and 21 bears S. 88° 34' W., 117.28 chs. dist., monumented with the original sandstone, 14 x 8 x 2 ins., mkd. 1/4 on one face, lying in a rock jack of about 20 smaller stones, in a wire fence which bears E. and W.

At the corner point:

Sent an iron post, 28 ins. long, 2 1/2 ins. diam., 12 ins. in the ground, to bedrock, supported in a mound of stone, 4 ft. base, to top with brass cap marked

1/4 $\frac{S\ 16}{S\ 21}$
T6N R37E
1965

Deposited original stone alongside the iron pipe.

No bearing trees available within limits.

Surveyor Paul W.P. Tomkins noted in his September 28, 1992 survey, shown on Umatilla County Survey record of surveys 92-122-B, "Fd. U.S.B.L.M. 2-1/2"x28"G.I.P. w/standard brass cap mkd. "1/4 S 16/S 21 T6n R37E 1965" in 4 ft. Dia. rock cairn in E/W barbed wire fence line."

Surveyor Paul W.P. Tomkins noted in his July 14, 2005 survey, shown on Umatilla County Survey record of surveys 05-134-C, "S 1/4 Cor. S 16, 3" BLM brass cap on 2 1/2" pipe, protruding 15" in rock mound."

Surveyor Paul W.P. Tomkins noted in his October 14, 2008 survey, shown on Umatilla County Survey Record of Plats 2008-29, BLM pipe and Br. Cap at 1/4 Cor. S16/S21."

MONUMENT AND ACCESSORIES FOUND:

Found 3 1/4 ins. BLM brass cap on 2 1/2 ins. pipe as noted by BLM, found in center of rock pile next to fence crib. Monument is +/- 1.5 ft. North of East/West barbed wire fence line.

MONUMENT MARKING DETAIL:

