

# OREGON CORNER RESTORATION FORM

COUNTY: Umatilla    DATE: 02/17/2015

**CORNER DESIGNATION:** N-15, Quarter Corner for Sections 15 and 22, Township 6 North, Range 37E, W.M.

**PREVIOUS RENEWALS/SURVEYS ETC:**

Originally surveyed by A. H. Simmons for US Deputy Surveyor George Williams under his contract No. 176 dated July 20, 1872. His notes state "Set stone 14 x 15 x 20 on steep side hill face W. for 1/4 Sec. Cor.

**MOUNUMENT AND ACCESSORIES FOUND:**

No evidence found

**MOUNUMENT MARKING DETAIL:**

LS 02820  
T6N R37E  
  
1/4 S 15  
S 22  
2/2015

**MOUNUMENT AND ACCESSORIES SET:**

At the surveyed position, set 2½ ins. brass cap on 1½" x 30" ins. galvanized iron pipe. 3 ins. above the ground stamped T 6N, R 37E, ¼ S15, S 22, 2/2015 LS 02820, from which:  
An 18 ins. in diam., fir, bears N. 61° W., 40.30 ft., blazed, scribed and tagged.  
A 14 ins. in diam., fir, bears N. 58° E., 39.70 ft., blazed, scribed and tagged.  
Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears S. 44° E., 18.00 ft.  
Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears S. 54° W., 24.00 ft.

**LOCATION AND COMMENTS:**

Bearings taken with Silva hand compass and distances measured with a steel tape.

**OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:**

N = 856112.27  
E = 8793180.56

**COMPASS DECLINATION:** 15° East

**SURVEYORS' SEAL:**

**FIRM:** HDJ Design Group  
5 N. Colville, Suite 200  
Walla Walla WA 99362

**WITNESSES:** Joseph R. Latimer  
Cory A. West



*Greg E. Flowers*  
OREGON  
JUNE 30, 1997  
GREG E. FLOWERS  
02820LS

RENEWS 12/31/15

*06/29/2015*