

MOUNUMENT MARKING DETAIL:



MOUNUMENT AND ACCESSORIES SET:

An 8 ins. diam., White fir bears S 42° W., 26.00 ft., blazed, scribed, tagged and painted, mkd.
T6N R37E S23 BT.

LOCATION AND COMMENTS:

Bearings taken with Silva hand compass and distances measured with a steel tape.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 856508.81
E = 8800972.35

COMPASS DECLINATION: 15° East

SURVEYORS' SEAL:

FIRM: HDJ Design Group
5 N. Colville, Suite 200
Walla Walla WA 99362

WITNESSES: Thomas J. Boshart
Felipe G. Hernandez



Greg E. Flowers
OREGON
JUNE 30, 1997
GREG E. FLOWERS
02820LS

RENEWS 12/31/15

06/29/2015

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 06/10/2014

CORNER DESIGNATION: N-21, Corner of Sections 13, 14, 23 and 24, Township 6 North, Range 37E, W.M.

PREVIOUS RENEWALS/SURVEYS ETC:

Originally surveyed by A. H. Simmons for US Deputy Surveyor George Williams under his contract No. 176 dated July 20, 1872. His notes state "Set post in mound with pits for Cor. to Sec. 13, 14, 23 and 24."

BLM Cadastral Surveyor C. Alfred White in his April 21, 1965 for Group 572, stated in his notes: Set an iron post, 28 ins. long, 2 ½ ins. diam., 22 ins. in the ground with a brass cap marked

T6N R37E	
S14	S13
<hr/>	
S23	S24
1965	

from which:

A Fir 13 ins. diam., bears N. 82½° E., 87 lks. dist., mkd. T6N R37E, S13 BT.

A Fir 18 ins. diam., bears S. 63° E., 29 lks. dist., mkd. T6N R37E, S24 BT.

A Fir 15 ins. diam., bears S. 15½° W., 43 lks. dist., mkd. T6N R37E, S23 BT.

A Fir 15 ins. diam., bears N. 48½° W, 132 lks. dist., mkd T6N R37E, S14 BT.

From this point the cor. of secs. 13, 18, 19 and 24, on the E. bdy. of the tp., bears S. 88° 33' E., 78.18 chs. dist., determined at record bearing and distance from the bearing tree mkd. by Wayne O. Harris, Umatilla County Surveyor, in 1961,

A yellow pine, 18 ins. diam., bears N. 73° E., 40 lks. dist. mkd. T6N R38E S18 BT, on a double blaze.

No permanent monument established.

MONUMENT AND ACCESSORIES FOUND:

Found a 3½ ins. BLM brass cap on a 2½ ins. iron pipe as noted by BLM Survey marked ¼ S23 and S24, T6N, R37E 1965, on a steep North facing slope with moderate underbrush and mature fir trees. The point is approximately 50 ft. S. of a creek bed ravine and approximately 40 ft. higher in elevation than the creek bed.

Fir tree 13 ins. diam., with healed blaze, no bearing tag found as noted by BLM, the tree is now 26 ins. diam., the tree was painted and tagged, bears N. 82½° E., 57.4 ft.

Fir tree 18 ins. diam., bears S. 63° E., 19.1 ft. dist., with healed blaze and bearing tag as noted by BLM. The tree is now 26 ins. diam., and was painted and tagged.

Fir tree 15 ins. diam. bears S. 15½° W., 28.4 ft. dist., as noted by BLM was found uprooted and down. The stump hole is at the BLM noted location and was accepted as bearing location.

Fir tree 15 ins. diam., bears N. 48½° W., 87.1 ft. dist., with healed blaze and bearing tag as noted by BLM. The tree is now 22 ins. diam., the tree was painted and said tree is across the creek bed ravine.