

Quarter Corner is located on a steep NE slope in heavy underbrush in moderate tree/timber area.
Bearings taken with Silva hand compass and distances measured with a steel tape.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 853866.61

E = 8800963.90

COMPASS DECLINATION: 15° East


SURVEYORS' SEAL:

FIRM: HDJ Design Group
5 N. Colville, Suite 200
Walla Walla WA 99362

WITNESSES: Thomas J. Boshart
Felipe G. Hernandez



Greg E. Flowers



RENEWS 12/31/15

06/29/2015

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla **DATE:** 06/10/2014

CORNER DESIGNATION: P-21, Quarter Corner Section for Sections 23 and 24, Township 6 North, Range 37E, W.M.


PREVIOUS RENEWALS/SURVEYS ETC:

Originally surveyed by A.H. Simmons for Deputy Surveyor George Williams under his contract No. 176 dated October 23, 1872; his notes state "Set post for ¼ Sec. Cor., from which:
A Red fir 12 in. dia., bears N 80° E., 64 lks. dist.
A Red fir 16 in. dia., bears N 65° W., 52 lks. dist.

BLM Cadastral Surveyor C. Alfred White in his April 21, 1965 Survey for Group 572, Oregon, states in his notes: "The ¼ sec. cor. of secs. 23 and 24, determined at record bearing and distance from the remains of the original NW, bearing tree:

A greatly decayed fir stump, 22 ins. diam., bears N 65° W., 52 lks. dist. Mkd. with a healed blaze, the wood behind decayed away. At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., in the ground with a brass cap mkd.



From which new bearing trees.

A fir 21 ins. diam., bears S. 68½° E., 76 lks. dist., mkd. ¼ S24 BT.

A fir 23 ins. diam., bears N. 60° E., 156 lks. dist., mkd. ¼ S23 BT.

MOUNUMENT AND ACCESSORIES FOUND:

Found 3½ in. BLM brass cap on a 2½ in. iron pipe as described by the 1965 BLM Survey.

Found as noted by BLM notes, the fir 21 ins. diam., bears S 68½° E., 50.1 ft. dist., mkd. ¼ S 24 BT. The fir is now 26 ins. diam.

The decayed remains of a 23" diam., fir stump and log bears N., 60° E 103 ft.

MOUNUMENT MARKING DETAIL:



MOUNUMENT AND ACCESSORIES SET:

A White fir 10 ins. diam., bears N 69° E., 24.80 ft. dist., blazed, scribed, tagged and painted. Mkd. "T6N R37E ¼ S24 BT"

A White fir 8 ins. diam., bears S 58° W., 23.20 ft. dist., blazed, scribed, tagged and painted. Mkd. "T6N R37E ¼ S23 BT"

A Douglas fir 6 ins. diam., bears N 27° W., 20.40 ft. dist., blazed, scribed, tagged and painted. Mkd. "T6N R37E ¼ S23 BT"

A "T" post with sign +/- 1.40 ft., downhill of monument.

LOCATION AND COMMENTS: